



### Telephone Memorandum

Project No.: 4	300 Client: Date: 5/19/44
Subject: エル	inois Cleany Requirement
Your Name: 🜙	Mark Crites
	Illinois EPA 217/782-6761
Rec'd Call ( )	
Comments	Summary of Conversation:
Illinois doesn't	Mark will send me Ill. Ground Water
accept PR6's	Evality Standards (Title 35, Part 620) couring
for soils unless	4 Classes of a guifer. Potable water aguifers
supported with	or close to Mills for the many chemicals spigneds
a risk assessment	
21.1. 01 7	named. Appendix has formulae based on Realth
Under Phase II	LUST site requirements (ostensibly Couring
cleampo tiel "Common serre";	BTEX, PNIt, lead).
these cleanups	There is no body of state regs like our 30%.
are usually met	Exiteria * are the default enteria. TCLP
reported to the	results one typically compand duelth to GW critain
State.	The above is the I'll approach to RCRIT
* metals only.	& CERCIA SItes.
Total organic concent	Too Ligital august tours be siles us
trations are correposed contract	hum a popular (1) laboration along the
CC.18 are consisted	Mints that satisfy lender or (2) pre-notice
	Atte monum involving state directly a with
	state signoff provision (you pay for the time
	the state remener sixents on your Project. The
	exemplice proposan Coordinator is Bob O'Hara, 1826762

THINOIS EPA

(Bir leavs) AIR LAND WATER (DIVIBIONS) [Dw. head vacuncy) LAND REMEDIAL POLLUTION MANAGEMT CONTROL CERCLA State Sugarfund [ Pre-notice] (All Solid Waste Phoxans (sections) (Sec. Head Vacancy) LAND PERMITTING (for sold & hazardov Hazaidous Waste Mark Crites, an Environmental Protection Engineer (title)

# TABLE 1 SUMMARY OF PHASE II FIELD SAMPLING AND ANALYSIS PROPOSED BY U.S. ARMY CORPS OF ENGINEERS WISCONSIN STEEL WORKS SITE

(Page 1 of 2)

	Task	Description	Number and Type of Sample	Analysis	Notes
1-	Deep Well Installation	10 wells to bedrock (approx. 70 feet bgs)	3 samples/well and 16 QA/QC samples	VOC, PAH, Pesticides, PCBs, CN, Total/Hex. Cr, Pb, As, Cd, Hg, Ni, Se, Zn	Samples will be taken at the locations showing the highest field screening levels.
1-	Shallow Well Installation	8 shallow sand wells (approx. 35 feet bgs)	2 samples/well and 10 QA/QC samples	Same as deep wells	Samples will be taken at the locations showing the highest field screening levels.
2-	Well Sampling	Sample 23 existing and 18 new wells	41 field samples and 18 QA/QC samples	VOC, PAH, Pesticides, PCBs, Phenol, Cn, NH <sub>3</sub> -N, Total/Hex Cr, Pb, As, Cd, Hg, Ni, Se, Zn, field parameters	All metals will be analyzed filtered and unfiltered
3-	Hot Spot Sampling	Approximately 900 feet of continuous sampling (45 borings to 20 feet)  45 ground water samples (hydropunch)  Possible soil gas analysis	95 soil samples 45 ground water samples No QA/QC samples	Analysis of soil samples vary by location, and may include analysis of PAHs, pesticides, PCBs, Pb, Cr, Cn, VOC, TPH, BTEX  Ground water samples are to be analyzed for PAH, pesticides, PCBs, VOCs, Pb, Cr (total)	The exact location of these samples has not yet been determined
4-	Background Sampling	Obtaining soil samples from nearby off-site locations at depths of 6 inches, 10 and 20 feet.	30 field samples and 14 QA/QC samples	VOC, PAH, Pesticides, PCBs, Phenol, Cn, NH <sub>3</sub> -N, Total/Hex Cr, Pb, As, Cd, Hg, Ni, Se, Zn	Permission for sampling will be necessary
5-	Conduit Sampling	21 sample locations in conduits, manholes, catch basins, etc.	29 water samples and 15 QA/QC samples  18 sediment samples and 9 QA/QC samples	VOC, PAH, Pesticides, PCBs, Phenol, Cn, Cr (total), Po, As, Cd, Hg, Ni, Se, Zn  Water analysis will also include NH <sub>3</sub> -N, Total/Hex Cr, Pb, As, Cd, Hg, Ni, Se, Zn	A seperate tracer study is also planned
6-	River/Slip Sampling	Continuous sampling at 11 locations to 20 feet bgs.	33 field samples and 19 QA/QC samples	VOC, PAH, Pesticides, PCBs, Phenol, Cn, NH <sub>3</sub> -N, Total/Hex Cr, Pb, As, Cd, Hg, Ni, Se, Zn	Samples are to be taken at the locations showing the highest field screening levels

## TABLE 1 SUMMARY OF PHASE II FIELD SAMPLING AND ANALYSIS PROPOSED BY U.S. ARMY CORPS OF ENGINEERS WISCONSIN STEEL WORKS SITE

(Page 2 of 2)

Task	Description	Number and Type of Sample	Analysis	Notes
7- TCLP Testing	Composite samples of slag and slag mixed with soil.  Composite sample from precipitator building foundations and sludge lagoons	Each composite sample will be taken from 4 subsamples 3 for slag and soil  1 foundation sample and 3 lagoon samples	TCLP metals for slag samples  All TCLP parameters for foundation and lagoons	
8- Aquifer Testing	Installation of two 6-inch wells, subsequent pump tests	Water levels, drawdown curve	None	The Phase I included testing of the sand and till units, with limited data for the till unit

#### Key:

As

Cd

= Arsenic

= Cadmium

bgs	=	Below ground surface.	Hg	=	Mercury
QA/QC	=	Qualityassurance/quality control.	Ni	=	Nickel
VOC	=	Volatile organic compound.	Se	=	Selenium
PAH	=	Polynuclear aromatic hydrocarbon.	Zn	=	Zinc
PCB	=	Polychlorinated biphenyl.	NH <sub>3</sub> -N	=	Ammonia nitrogen
CN	=	Cyanide	TPH	=	Total petroleum hydrocarbons
Total Hex Cr	=	Total hexavalent chromium	BTEX	=	Benzene, toluene, ethylene, xylene.
Pb	=	Lead	TCLP	=	Total characteristic leaching procedure.

#### TABLE 2 SUMMARY OF HOT SPOT SAMPLING WISCONSIN STEEL WORKS

	Number of		Number of Screening	РАН		Pesticides		PCBs		Pb/Cr		VOC		ТРН		втех		CN	
Area ID	Area Description	Samples in SOW	Samples Proposed by ERM <sup>(1)</sup>	SOW <sup>(2)</sup>	ERM <sup>(3)</sup>														
1a	Discarded tanks near SS-20	2	8 - 16	х				х		Х					Х				
2a	Steel Finishing Area, near SB-14, F-15	6	8 - 16	Х	Х	Х		Х		Х		Х			X				
2b	Steel Finishing Area near SB-10, S13-11	6	24 - 48		Х	Х		Х		х	Х								Х
2c	Filled in Slip	12	16 - 32		X	х		X		х	Х				Х				
2d	Lagoons & South of Mill 6	12	16 - 32		Х					х	Х			Х	х				
3a	Blast Furnace Area, near MW-16	4	16 - 32	Х	Х					х				X	х				
3b	Former Stripper building near SB-09	4	8 - 16		Х	Х		Х	Х	х									Х
4	Steel Production Area	20	48 - 96	Х	Х	Х		Х		Х	х	х	Х	,	Х			-	Х
5	Coke Plant/Coal Storage Area	30	56 - 112	Х	Х	Х		Х	Х	Х	Х		Х		Х	Х		Х	Х
NA	Office Area	0	8 - 16		1						Х								
NA	Ore Yard	0	8 - 16		Х														
Total	Number of Samples	96	216 - 432																

#### Notes

- (1) At least 8 samples will be obtained for screening from each sample origin. For estimating purposes, it is assumed that each 16 samples will be associated with each sample origin.
   (2) This area specified for sampling in the SOW
   (3) ERM suggests that sampling occur in or near the area designated in the SOW

Scope of Work for Phase II Sampling and Analysis, prepared by the US Army Corps of Engineers, February 1994. Polynuclear aromatic hydrocarbons

Lead

Chromium

Volatile organic compounds VOC = TPH =

Total petroleum hydrocarbons Benzene, toluene, ethylbenzene and xylene BTEX =

#### **WISCONSIN STEEL**

#### PHASE II RI

#### FIELD STUDIES

#### TASK 1 - Additional Wells

- \* 9 Deep Wells (Rock Surface or into Rock?)
- \* 7 Shallow (4 water table) heeds more

#### TASK 2 - Sampling Wells

- \* 23 existing, 16 new
- \* One sampling event ->
- \* Parameters Volatile Organics, PAH's, Pesticides/PCB's, Phenol, Cyanide, NH<sub>3</sub>-N, Metals (**1**otal, Hex Chrome, Lead, Arsenic, Cadmium, Mercury, Nickel, Selenium, Zinc, pH, Conductivity

#### TASK 3 - Hot Spot Demarcation and Sampling

\* General areas shown in Fig. 2-3 (p.2-13,2-14) and Table 2-7 (p.2-19) of SOW

#### TASK 4 - Background Soils (Optional)

- \* 10 locations in parks, cemeteries, school yards, etc.
- \* Same parameters as wells

#### TASK 5 - Sampling/Analyses of sediments, water from:

- \* Conduits, manholes, outfalls, basins, and tracer studies
- \* Same parameters as wells

#### TASK 6 - Deep Core Sampling from Calumet River and Slips

- \* 11 core locations (Fig. 2-6, p.2-27, 2-28) (4 from slips, 7 from river)
- \* Same parameters as wells


#### TASK 7 - Additional TCLP Testing


- )TCLP Metals Only \* 3 slag
- \* 3 weathered slag/soil
- \* Lagoon sludges, precipitator sludge all TCLP parameters

#### TASK 8 - Pump Tests

- \* Slag area \* Water Treatment Plant area

RISK ASSESSMENT





### TABLE 2-7 POTENTIAL HOT SPOT SAMPLING AND DEMARCATION ESTIMATED NUMBERS OF SAMPLES

- 1. Slag Area
- 1.a Discard tanks near SS-20

<u>Parameters</u> - PAH's, PCB's, lead, chromium Estimated no. confirmatory lab samples - 2

- 2. Steel Finishing Area
- 2.a SB-14, F-15 (oil sheen observed during SB-14) boring PCB's detected, diesel fuel odor in ground water near F-15).

<u>Parameters</u> - PAH's pesticides/PCB's, volatile organics, lead, chromium. Estimated no. confirmatory lab samples - 6

2.b SB-10, SB-11 (Pesticides, PCb's detected)

<u>Parameters</u> - Pesticides/PCB's, lead, chromium Estimated no. confirmatory samples - 6

2.e Filled in slip (SB-12, High PAH's, PCB's, chromium, MW-13, elevated metals (pb, Cr, Zn) should determine boundaries and character of deep fill

<u>Parameters</u> - Pesticides/PCB's, lead, chromium Estimated no. confirmatory lab samples - 12

2.d Lagoons & vicinity south of Mill #6 (SB-13, SS05, SS06, SS07 high lead, chromium, SS05, 06, 07 high TPH)

<u>Parameters</u> - Lead, chromium, TPH Estimated no confirmatory lab samples - 12

- 3. Blast Furnace Area
- 3a. MW-16 (Deep Fill Layer 0-25', High PAH's, TPH)

<u>Parameters</u> - PAH's, TPH, lead, chromium Est. No. confirmatory samples - 4

3b. SB-09 former stripper building (~15 Feet Fill, PCB's Detected, Pesticides Detected at 25-27', PID-250 ppm)

<u>Parameters</u> - PCB's/Pesticides, lead, chromium, volatile organics Est. No. confirmatory lab samples - 4

## TABLE 2-7 POTENTIAL HOT SPOT SAMPLING AND DEMARCATION ESTIMATED NUMBERS OF SAMPLES (continued)

#### 4. Steel Production Area


4a. Basic oxygen furnace/precipitator/benzol building (fill/soils in this area have PCB/Pesticide (chlordane), PAH's, petroleum hydrocarbon contamination. MW-5 water has oily phase with BTEX, PAH's, solvents, pesticides, MW-20 water high BTEX)


<u>Parameters</u> - PCB's/Pesticides, PAH's, volatile organics, lead, chromium Est. No. confirmatory samples - 20

5.

5a. Coke Plant/Coal Storage Area (Fill and soils in these areas have high levels of PAH's, BTEX; metals; PCB's detected; oily sludge observed in SB-03; black discoloration and oil sheen in SB-02 TO 25'; visible oil contamination and highly elevated PAH's in fill and sand to 20+ feet at MW-19; SB-02 had elevated PAH's in sand at 11-13' with black discoloration and oil sheen to 25'; elevated PAH's and PCB's in MW-25 boring to 25'.) It is important that one or more samples be taken in the vicinity of the former gas holder.

<u>Parameters</u> PAH's, BTEX, PCB's/Pesticides, volatile organics, lead, chrome, cyanide Est. No. confirmatory samples - 30





#### WISCONSIN STEEL WORKS SITE Chicago, Illinois

#### BUFFALO DISTRICT-EDA STRATEGY MEETING FOR THE PHASE II FIELD SAMPLING/ANALYSIS

PURPOSE: For discussion at the Technical Meeting on May 13, 1994, to resolve all comments to the Phase II Field Sampling/Analysis Scope of Work (SOW).

#### Buffalo's Evaluation of All Cmts Received

	On '	The Phase II	BOW	
Discussion Items For 10 May 94	NAVISTAR	CORPS (NCB/MRD)	<u>IEPA</u>	<u>USEPA</u>
1. ITEMS IN SOW - Deep Wells	N/D	Y	Y	Υ_
<ul><li>Pumping Tests</li><li>Sample CBs, MHs,</li></ul>	N/W	N/D	N	7 7
Cond/Outfalls	N/D	Y	Y	?
<ul><li>Tracer Study</li><li>Samplg Calumet,</li></ul>	<b>*</b> \	Y	Y	Y
N & S Slips	N	Y	Y	Y
- TCLP	N	Y (exc. slag)	Y	?
- Risk Assessmnt	4FW 7	Y	?	?
- Background Soil	N	?	Y	Υ_
- Background Wells	N	Y(us4s)	Y	Y
2. Ph III Requiremnt	N*	Ň	N	N

[\* - However, the Corps disagrees with NAVISTAR'S conclusion that if their comments are incorporated into the SOW there will be no additional data collection after Phase II. A Phase III would almost be a certainty since the items identified in their comments to be delayed in 1. above (N/D) are all essential to the completion of the Remedial Investigation (RI)].

3. Overall Savings	Y OF	oe N	?	?
4. Delay in RI	1 - 1 1/2 yrs.	Hold Schedule	?	?
5. Cost Estimates (Ball	Park \$ X	1000)		
- NAVISTAR SOW	-	\$530	_	-
- CORPS SOW	-	750	_	_

**D-**Would Delay RI Report; **N-**Should be deleted from SOW; **Y-**Should Stay in SOW; **?-**Unknown Position or Unclear